GOVERNMENT OF KERALA

Abstract

Public Works Department - Administrative Sanction for the work " Budget work 2024-25 - General - BW - 2024-25 (20% provision) Upgradation (with BM & BC - 5.500 km) Improvements to Kalpathur Velliyoor - Kappummal road - Ch 0/000 - 3/300 and 3/800 - 6/000 in Kozhikode District - General Civil Work - Accorded - Orders Issued

---

PUBLIC WORKS (PS) DEPARTMENT

G.O.(Rt)No.346/2026/PWD Thiruvananthapuram, Dated, 06-03-2026

Read Letter No: CEPWD/1383/2025-DB4(PL)-RD Dated 20.07.2025 & 31.07.2025 from the Chief Engineer, Public Work (Roads), Thiruvananthapuram

ORDER

The Chief Engineer, Public Work (Roads), as per his letter read above, has submitted a proposal for granting Administrative Sanction for the "GENERAL - BW 2024-25 (20% provision) - Upgradation (With BM & BC -5.500 km) Improvements to Kalpathur Velliyoor - Kappummal road - ch 0/000 - 3/300 and 3/800 - 6/000 in Kozhikode District - General Civil Work" for an amount of ₹ 1000 Lakh under the head of account 5054-04-337-99.

2) Government have examined the matter in detail and pleased to accord Administrative Sanction for the 20% work "Budget work 2024-2025- General - BW - 2024-25 (20% provision) Upgradation (with BM & BC - 5.500 km) Improvements to Kalpathur Velliyoor - Kappummal road - Ch 0/000 - 3/300 and 3/800 - 6/000 in Kozhikode District - General Civil Work " for an amount of ₹ 1000 Lakh (Rupees

Ten Crore only) under the head of account 5054-04-337-99 based on DSoR 2021 subject to the compliance of following conditions while issuing the Technical Sanction.

1) The scarified or dismantled pavement layers shall be re-used below the GSB layer as sub base or at shoulders with proper compaction. The thickness of GSB layer in the carriageway shall be reduced accordingly.

2) The thickness of existing pavement crust shall be taken into account while proposing the total pavement thickness. The thickness of fresh GSB & WMM, if any required, shall be optimized to the normal provisions.

3) The provision for shoulder concrete, berm concrete, Irish drain, etc. shall be allowed as shoulder protection in essential stretches like gradients and curves ONLY and for a minimum width of 50 CM only.

4) The proposals for RCC cover slabs for drains, Foot paths with Paver blocks or Tiles, GI pipe hand rails, etc. shall be allowed in technically justified locations only.

5) The CC Side protection walls shall be substituted with DRM and RCC belt as stipulated in Govt. Circular No.64/2021/Fin dated 05/08/2021.

6) Proper account of re-usable / serviceable materials obtained from dismantling items of work shall be ensured.

7) The provisions for Road furniture shall be regulated as per IRC guidelines after assessment of existing items available at site. Proper account (Register) shall be maintained for the road furniture items.

8) The provisions for construction of culverts shall be regulated as per IRC guidelines.

9) Defect liability period/Running Contract of the proposed road reach shall be ensured. Also, duplication of proposals under different

schemes for the same reach shall be avoided.

10) The correctness of the rates adopted for observed data's included in the estimates shall be ensured by the TS authority.

11) In cases where dismantling of existing DR masonry structures is necessitated as per site conditions, its chainage shall be clearly specified in the M-Book and the rubble so obtained shall be reused properly and accounted as departmental rubble.

12) As the KWA restoration works are in progress on both sides of Kalpathur Velliyoor - Kappummal road ch 0/000 - 3/300 and 3/800 - 6/000, the road improvements work can be considered only after expiry of road restoration works.

(By order of the Governor)
K BIJU I A S
SECRETARY

The Chief Engineer, Public Work (Roads), Thiruvananthapuram
The Principal Accountant General (A&E/Audit), Kerala, Thiruvananthapuram

The Accountant General, (A&E/Audit), Kerala, Thrissur

The Finance Department (E 3341086 INPWC1/131/2025-FIN dated, 28.02.2026)

The Information&Public Relations (Web and New Media) Department

Stock File (PS2/397/2025/PWD)

Forwarded /By order
Signed by
Aneesh S
Date: 07-03-2026 13:42:40
Section Officer