GOVERNMENT OF KERALA

Abstract

Public Works Department – Improvements to Puthanpalli Munakkal Beach Road from Ch. 0/000 to 2/300 and Beautification of Azhikkode Munakkal beach in Eriyad Grama Panchayath (20% provision allocation)-in Kaipamangalam LAC - Administrative Sanction Accorded - Orders issued.

PUBLIC WORKS (G) DEPARTMENT

G.O.(Rt)No.254/2026/PWD Dated,Thiruvananthapuram, 21-02-2026

Read 1 Letter No. CEPWD/9063/2025-DB5(PL)-RD / AS Committee/2025 -26 (Plan) dated 21-10-2025 from the Chief Engineer, PWD Roads Division, Thiruvananthapuram

2 Minutes of the Administrative Sanction Committee meeting held on 23.10.2025

ORDER

The Chief Engineer (Roads) as per his letter read above has furnished an estimate report for the work "Improvements to Puthanpalli Munakkal Beach Road from Ch. 0/000 to 2/300 and Beautification of Azhikkode Munakkal beach in Eriyad Grama Panchayath (20% provision allocation)-in Kaipamangalam LAC, based on DSoR 2021, for an amount of ₹600 Lakhs for Administrative Sanction.

2. Government have examined the matter in detail and are pleased to accord Administrative Sanction for the work "Improvements to Puthanpalli Munakkal Beach Road from Ch. 0/000 to 2/300 and Beautification of Azhikkode Munakkal beach in Eriyad Grama Panchayath (20% provision allocation)-in Kaipamangalam LAC for an amount of ₹600 Lakhs (Rupees Six hundred Lakhs Only) under

the Head of Account ‘ 5054-04-337-99-MDR’ subject to the following conditions:

1.The proposal for improvement with BM & BC may be done with due consideration for importance of road and traffic density only. In other cases, possibility of substituting the BM & BC with MSS ‘wearing course may be explored.

2.Scarification of existing bituminous layer or dismantling flexible pavement may be adopted in severely damaged and gradient correction portions only.

3.The scarified or dismantled pavement layers shall be re-used below GSB layer as sub base or at shoulders with proper compaction. The thickness of GSB layer in the carriageway may be reduced proportionately.

4.The thickness of GSB may be optimized to the normal provision of 15cm to 20cm.

5.Side protection walls with PCC may be substituted with DRM and RCC belt as stipulated in Govt. Circular No.64/2021/Fin dated 05/08/2021.

6. Proper account of re-usable materials obtained from dismantling items of work shall be ensured

7. The provisions for Road furniture shall be regulated as per IRC guidelines after assessment of existing items available at site. Proper account (Register)shall be maintained for the road furniture items.

8. The provisions for construction of culverts shall be regulated as per IRC guidelines. Defect liability period of the proposed road reach shall be ensured. Also, duplication of proposals under different schemes for the same reach may be avoided.

9. During TS issue , the total LS amount of Rs 1,00,25,000/-, shall be replaced with detailed estimate and reporting items shall be done for required items, with covering letter.

10. The Provision for quarry muck,GSB and WMM below interlock

tiles should be limited to GSB only.

A copy of TS estimate shall be forwarded to CTE by mail before call of tenders.

(By order of the Governor)
SUMESH KUMAR C
JOINT SECRETARY

To:
The Chief Engineer, Public Works Department (Roads), Thiruvananthapuram
The Superintending Engineer, Public Works Department (Roads), Central Circle, Aluva
The Executive Engineer, Public Works Department, Roads Division, Thrissur
The Accountant General (A&E/Audit) Kerala, Thiruvananthapuram
Finance Department (INPWC1/128/2025-FIN (E 3338368)dt. 16/02/2026)
Stock File/Website

Forwarded /By order

Signed by
Savitha o.d
Date: 21-02-2026 16:47:36
Section Officer